



Internal Technical Report

**Efficient Cooling Arrangement and Integration of
30 antenna GWB system for
uGMRT Digital Backend**

Mr. Irappa M. Halagali

irappa@gmrt.ncra.tifr.res.in

and

Mr. Ajith Kumar B.

ajit@ncra.tifr.res.in

Group Head, Digital Backend

Prof. Yashwant Gupta

ygupta@ncra.tifr.res.in

Dean, GMRT

Document history :

Revision	Date	Modification / Change
Ver. 1.0	14/05/2017	Initial version (consolidated various reports on cooling & integration on GWB system.

Objective :

To propose a suitable cooling arrangement for the new Digital Backend system GWB (GMRT Wideband Backend) for the uGMRT receiver, so that the system can co-exist with the GMRT Software Backend (GSB) in the correlator room at Central electronics building (CEB).

Also to propose a suitable rack with efficient cooling arrangements for the GWB system and to provide in-depth details about the integration of GWB system.

Index

	Page Number
A. Introduction	3
B. Efficient Cooling Study	5
1 AC plant and distribution layout	6
2 Correlator Room Floor diagram	7
3 Theoretical Calculations	8
4 Practical Measurements	10
5 Air flow measurement using anemometer	11
6 Summary of experiment results	12
C. Power Consumption Study	13
1 Units/Instruments in the GWB System.	13
2 GWB Modelwise Power Consumption	15
3 GWB Rackwise Power Consumption	15
4 Measurement of Power Consumption	16
D. GWB System Integration	18
1 Racks requirement, configuration and modifications .	18
2 Units and specifications	21
3 Units placement in the Racks	24
4 Racks placement in the correlator room	25
5 Cool air utilization in the correlator room	30
6 Bill of material	31
7 Electrical connections	32
8 Inter rack connections	32
9 Intra rack connections	33
10 Integration of system	33
11 SOP's and Testing	35
E. Conclusion	36
Appendices :	
1 Auto calculator	37
2 Experiment setup details	38
3 Summary of Daily readings	39
4 Average of Daily readings	40
5 Daily Readings	47
6 Air Flow meter User Manual	47


A. Introduction.


GWB system.

As part of GMRT upgradation (uGMRT), the back-end systems are undergoing major changes to achieve the specifications like increased bandwidth of 400MHz, direct processing of RF signals, increased dynamic range, improved channel resolution. The digital backend part of this upgrade named as GWB(GMRT WIDEBAND BACKEND). This is a 30-antenna dual polarization correlator.

The design is a hybrid one using FPGAs and CPU-GPUs for various processes in the digital back-end chain. FPGAs connected with ADCs perform the digitisation and packetising the data, while CPU-GPUs acquire the data, perform correlation and record the visibilities and beamformer output data onto a disk for post-processing and analysis. The implementation is a time-slicing model, where each compute node gets a slice of contiguous time series data from all the antennas, on which it performs spectral conversion, correlation and Incoherent Array (IA) and/or Phased Array (PA) beamformation operations. For narrowband mode observations, the data is digitally down-converted and decimated before the spectral conversion stage. Dedicated 10 Gigabit Ethernet links are used for transferring digitized data from the FPGAs to the compute nodes, while a 40 Gbps Infiniband network is used for both redistribution of data for time slicing, and gathering of results onto the host nodes for final recording. Figure 1 shows the top level design of the GWB.

Block Diagrams :





Study of efficient cooling, electrical power consumption and integration of GWB system.

To accommodate the 30 antennae GPU based GWB system with the existing GSB system in the correlator room, it was necessary to do a detailed study of the power consumption, efficient cooling and specifications & placement of the racks in the correlator room.

This report is to document all the calculations, tests, measurements and analysis done before integrating, testing and releasing the GWB system for astronomical use. This report also documents about the units, cables etc.. used in the system. And also explains the factors considered in deciding the various things like placement of units in the racks, cables movement within & inter racks, provisions for future expansions, utilization of infrastructure etc.. to achieve the following things :

1. Use the infrastructure available with us to it's best, in such a way that, we will be able to meet our specific goals & expectations.
2. By doing simple modifications / additions to racks, bring down the cost of racks to be acquired.
3. Reduce the running cost of AC plant by utilizing the cool air efficiently. And
4. Reduce the failure of components by providing sufficient & regular cooling at all points in a rack and all the time.

B. Efficient Cooling Study :

To accommodate the 30 antennae GPU based GWB system with the existing GSB system in the correlator room, it was necessary to do a detailed study of the power consumption, efficient cooling and specifications & placement of the racks in the correlator room.


Started with the theoretical calculations of the cool air flow at each outlet. Capacity of AC plant is 1300 cfm (Cubic Feet per Minute). The cool air coming out from the AC plant is split between correlator and receiver rooms in the ratio of 70:30. By considering 90% efficiency of the AC plant and 20% leakages in the duct, the air reaching the correlator room is 6,000cfm. There are 6 ducts in the correlator room. So 1,000 cfm of cool air is expected from each outlet.

To study the cool air flow, specifications and design of the racks to be procured, one rack of 42U (HxWxD - 2065mm x 600mm x 1000mm) has been modified to carry out the heat load test. And also to decide the placement of units in the rack and placement of racks in the correlator room. 4 hallogen lamps of 1KW each have been used for this test.

Aim was to findout the cool air available at various locations & it's heat absorption capacity, which depends on the humidity and temperature of the cool air. And thereby deciding whether this is sufficient to dissipate the heat, which will be generated by 30 antennae GWB system. If cool air is not sufficient, ways to achieve it. Also to decide the placement of racks in the correlator room by considering various factors like cool air inlets, hot air exhausts, cables movement mainly inter racks and space for man-meterial movements.


These theoretical and practical calculations were re-evaluated using the air flow meter. Finally all the calculations, expreriment results and measured values are matching.

1. AC distribution layout.



**AC Plant : Air Handling Unit (AHU) capacity
13,000 Cubic Feet per Minute (CFM).**

2. Correlator Room Floor diagram.



Note : outlet rooftop duct number 2 has been moved at above the floor tile number 75 in the month of October 2016 to facilitate the outlet hot air from GWB racks 1 & 2 to go out through hot air duct.

So mass of cool air reaching corr. Room = $1.128666667 \text{ mtr}^3/\text{min} \times 169.92 \text{ kg/mtr}^3$
 $= 191.783040057 \text{ kg/min.}$

b. "Specific Heat of air = 240 calories/kg degree celsius.
 @ temp. of 20degree cel. & pressure of 1 pascal

www.usc.edu/org/.../Heat%20Capacity%20and%20Specific%20Heat.pdf , http://www.engineeringtoolbox.com/specific-heat-capacity-d_391.html

c. "Diff. in temperature of corr. Room = $25 - 10 = 15$ degree celsius

So,

Heat Absorption of the cool air = $191.783040057 \text{ kg/min} \times 240 \text{ Calories/kg per DegCel} \times 15 \text{ DegCel}$
 $= 6,90,419 \text{ calories/min.}$

So,

Heat Absorption of the cool air from each outlet in the correlator room = $6,90,419 / 6 = 1,15,070 \text{ Calories/min.}$

Conclusion :

a. Heat absorption of cool air from each inlet of 1000 CFM and inlet to outlet temperature difference of 15 DegCel is 1,15,070 Calories/minute.

b. So to absorb 3,08,185 calories/min. of heat generated by GWB system, we need 2.68 (308185÷115070) cool air inlets. Each inlet of 1000 CFM cool air.

4. Practical Measurements.

For this practical measurements, we have used the Heat load of 4000 Watts. Maximum GWB power consumption is 21,500 watts or 3,08,185 calories/minute(refer "GWB rackwise power consumption").

A. Using 3 fans of 100cfm each to suck the cool air in the aluminium cage in the rack.

We got the temperature difference of 15.5 degreeCel. So
Volume of cool air per inlet in the correlator room is 482 Cubic Feet/Minute instead of 1000CFM !!!

Total Heat Energy --> 3,08,185 calories/minute
Heat Absorption by 482cfm Cool Air --> 57,312 calories/minute
So 5.38 inlets with cool air of 482 CFM are required !!!

B. Using 2 fans of 600cfm each to suck the cool air in the aluminium cage in the rack.

If these fans are at 2' height of the al. cage, then the temperature difference is 5.4 degCel.
If moved these fans at the bottom of the rack and kept this 2' height slot in the al. cage open, then the temperature difference is 9.21degCel. This temperature increases by around 1 degCel, if we put 3 fans of 100cfm each at the open slot in the al. cage!


If we take 5.4 degCel., then

- a. Volume of cool air per inlet in the correlator room is 1384 CFM.
- b. Heat Absorption by 1384 CFM Cool Air is 1,64,565 calories/minute.
- c. So 1.87 inlets with cool air of 1384 CFM are required.

If we take 9.21 degCel., then

- a. Volume of cool air per inlet in the correlator room is 812 CFM.
- b. Heat Absorption by 812 CFM Cool Air is 96,551 calories/minute.
- c. So 3.19 inlets with cool air of 812 CFM are required.

5. Air flow measurement using anemometer.



For air flow measurement in the correlator room, we have used “ Pitot Tube Anemometer + Differential Manometer HD350” from Extech Instruments. Measured the air flow volume over the duct number 1 and 3. Using this meter, we measured air flow at 5 points in the duct (4 corners and at the centre about half a foot height) and took average of those readings. It was around 1600cfm & 1200cfm from duct number 1 & 3 respectively.

Detailed measurement of air flow from AC plant to end points in Correlator & Receiver rooms needs to be done at various possible locations. This will give the complete and exact know how about the cool air volume at different locations and leakages.

The air flow measurement procedure is explained in appendix “VI Air Flow Meter User Manual”


6. Summary of experiment results.

A quick summary of the test results is,

a. for a power dissipation of about 4KW per rack (refer topics“4. GWB modelwise & 5. GWB rackwise Power Consumption”), the maximum outlet air temperature will be of the order of about 25 degCel., while the maximum inlet temperature is 10 degCel. More details are given in Appendix 3 : Summary of Daily Readings.

b. Volume of cool air from each duct in correlator room as per theoretical assumption is 1000cfm. It is 1600cfm as per the measurement done using air flow meter over the duct at duct no. 1 (which is 1200cfm over duct no. 3). As per the setup 3a (refer apendix II experiment setup details) , we gets a temperature difference of 9.21DegCel. This results in the volume of cool air as 812cfm. The cool air volume using meter is around 600cfm(5' away from the duct).

Test Setup image



by Irappa M. Halagali, Digital Backend, GMRT

C. Power Consumption Study.


The theoretical calculations of electrical power consumption was done by refering the datasheets of each units being used in the GWB system. How many racks are required and what is the maximum and typical heat generated from each rack. Units are distributed between the racks such that the heat generated from each rack should be almost equal and also considered other factor like internal and intra rack cables, space for future expansions/changes etc.. By considering all these points, we have decided to have 6 racks for the GWB system. The power consumption from each rack restricted to around 2.5 KW and 0.5 KW for addition in future. 20KVA UPS is feeding electrical power to the whole GWB system along with some test setups. To be safer side, we shouldn't drawn more than 16KVA ie 80% of 20KVA from this UPS.

We have measured the electrical power consumption by each GWB rack. With correlator code running, the power consumption fluctuates between 60% to 83%, and when the system isn't under use, it is around 54%.

1. Units/Instruments in the GWB System.

Rack No.	GWB 30 Antenna System	
	Rack Name	Model/Unit Names
1	Pol.1 : C sq + E2 & E3 antenna's	Dell T620/T630 with K20/40 GPU cards - 4 nos., Dell T630 -1 no., ROACH unis with 2 iADC cards – 4 nos., .100 n/w ethernet s/w – 1 no. and Clock & Trigger Distribution unit -1 no., & Fans of 360cfm – 4nos.
2	Pol.2 : C sq + E2 & E3 antenna's	Dell T620/T630 with K20/40 GPU cards - 4 nos., ROACH unis with 2 iADC cards – 4 nos., .100 n/w ethernet s/w – 1 no. and Clock & Trigger Distribution unit -1 no., & Fans of 360cfm – 4nos.
3	Host Machines (Recording)	Dell T620/T630/T7500 w/o K20/40- 5 nos., .4 & .100 n/w eth. s/w – 1 no each., Infiniband 36p s/w–1no.,& Dell PER210 - 1no., HDD's&Fans of 360cfm–4nos.
4	Host Machines (Monitoring)	Dell T620/T630 w/o K20/40- 5 nos., .4 n/w switch – 1no., Clock and Trigger Master unit -1 no., PC's for temp monitor., & Fans of 360cfm – 4nos.
5	Pol. 1 : E4 to E6 and S & W arm antenna's	Dell T620/T630 with K20/40 GPU cards - 4 nos., ROACH unis with 2 iADC cards – 4 nos., .100 n/w ethernet s/w – 1 no. and Clock & Trigger Distribution unit -1 no., & Fans of 360cfm – 4nos.
6	Pol. 2 : E4 to E6 and S & W arm antenna's	Dell T620/T630 with K20/40 GPU cards - 4 nos., ROACH unis with 2 iADC cards – 4 nos., .100 n/w ethernet s/w – 1 no., and Clock & Trigger Distribution unit -1 no., & Fans of 360cfm – 4nos.
7 & 8	Misc..	Extensions 1 & 2 (Pocketized correlator etc...) & Tube lights.

An image depicting the units in the GWB racks.



gwbcorr node machines are Dell T620/T630.
 .100 n/w eth. s/w. at rear side of clk/trig. unit in each rack.

host m/c's are Dell T620/T7500.
 .4 n/w eth. s/w. at rear side of .100 n/w eth s/w.

host m/c's are Dell T620/T7500.
 GWBUnitsInRacks.fig
 IMH 10/07/2017.

2. GWB Modelwise Power Consumption.

As per the datasheets or webpages the power consumption of the units used in the GWB system mentioned below.

Model wise Power consumption by GWB 30 Ant. System.

Model Name	Power Consumption/Model		Total Models	Total Power Consumption	
	Typical	Maximum		Typical	Maximum
Dell T620 Nodes	369	628	16	5,904	10,048
Dell T620 Hosts	369	628	3	1,107	1,884
K20 GPU Cards	105	225	32	3,360	7,200
Myricom 10GbE Single Port	5	5	32	160	160
Melox infiniband NIC card	2	2	19	38	38
ROACH Board (1 ADC)	50	60	32	1,600	1,920
ADC in ROACH Boards	1.5	1.5	32	48	48
Melox infiniband 32P Switch	3	3	1	3	3
Signal Generator (N9310A)	65	65	1	65	65
PPS unit & misc..	50	100	1	50	100
G. Total				12,335	21,466

3. GWB Rackwise Power Consumption.

As per datasheets ..

Rack wise Power consumption by GWB 30 Ant. System.

Rack Number	Model Name	Power Consumption/Model		Total Models	Total Power Consumption	
		Typical	Maximum		Typical	Maximum
1 to 4	Dell T620 Nodes	369	628	4	1,476	2,512
	K20 GPU Cards	105	225	8	840	1,800
	Myricom 10GbE Single Port	5	5	8	40	40
	Melox infiniband NIC card	2	2	4	8	8
	ROACH Board (1 ADC)	50	60	8	400	480
	ADC in ROACH Boards	1.5	1.5	8	12	12
Sub Total 1					2,776	4,852
5	Dell T620 Hosts	369	628	3	1,107	1,884
	Melox infiniband NIC card	2	2	3	6	6
	Melox infiniband 32P Switch	3	3	1	3	3
	Signal Generator (N9310A)	65	65	1	65	65
	PPS unit & misc..	50	100	1	50	100
Sub Total 2					1,231	2,058
G. Total					12,335	21,466

4. Measurement of Power Consumption.

Measurement of electric power usage by the correlator systems. PF = 0.8

A. GWB system :

UPS 1 , max. 78% of 20 KVA, under use for tests ie 15.6KVA or 12.48 KWatts.
 Row 1 (Top) : 29.2 Amps and Row 2 (Bottom) : 32.1 Amps Total : 61.3# Amps
 61.3Amps * 230Volts = 14.099 KVA OR 11.28 KWatts ie 71%

Sl. No.	Distribution board	Current in Amps	Remarks
1	GWB rack-1 : ROW1(top), MCB No. 1	12.2	P=0.8*12.2*230=2245 wats
2	GWB rack-2 : ROW1(top), MCB No. 2	10.6	
3	GWB rack-3 : ROW1(top), MCB No. 3	3.6	
4	Ext Board 1 : ROW1(top), MCB No. 4	0.6	
5	GWB rack-4 : ROW2(top), MCB No. 1	7.9	
6	GWB rack-5 : ROW2(top), MCB No. 2	10.1	
7	GWB rack-6 : ROW2(top), MCB No. 3	10.6	
8	Ext Board 2 : ROW2(top), MCB No. 4	2.4	
	Grand Total	60.0*	

B. GSB system :

UPS 3 , max.64% of 12.5 KVA, under use for tests ie 8KVA or 6.4 KWatts
 Row 1 (Only) : 29.8# Amps
 29.8 Amps * 230Volts = 6.854 KVA OR 5.483 KWatts ie 55%

Sl. No.	Distribution board	Current in Amps	Remarks
1	GSB EXT 1 : ROW1, MCB No. 1	0.5	
2	GSB rack-1(EB1) : ROW1, MCB No. 2	4.0	
3	GSB rack-1(EB2) : ROW1, MCB No. 3	6.4	
4	GSB EXT 2 : ROW1, MCB No. 4	0.9	
5	GSB rack-4(EB3) : ROW1, MCB No. 5	6.1	
6	GSB EXT 4 : ROW1, MCB No. 6	1.9	
7	GSB rack-4(EB2) : ROW1, MCB No. 7	1.8	
8	GSB rack-4(EB1) : ROW1, MCB No. 8	3.7	
	Grand Total	25.3*	

UPS 2 , 56% of 20 KVA, under use for tests ie 11.27 KVA or 8.96 KWatts
 Row 1 (Top) : 27.8 Amps and Row 2 (Bottom) : 17.0 Amps Total : 44.8 Amps#
 44.8 Amps * 230Volts = 10.304 KVA OR 8.2432 KWatts ie 41.2%

Sl. No.	Distribution board	Current in Amps	Remarks
1	GSB rack-2(EB3) : ROW1(top), MCB No. 1	7.3	
2	GSB rack-3(EB1) : ROW1(top), MCB No. 2	5.8	
3	GSB rack-2(EB1) : ROW1(top), MCB No. 3	5.8	
4	GSB EXT 1 : ROW1(top), MCB No. 4	1.6	
5	GSB EXT 2 : ROW1(top), MCB No. 5	--	
6	GSB EXT 26 : ROW1(top), MCB No. 6	2.1	
7	GSB EXT 27 : ROW1(top), MCB No. 7	0.7	
8	Lamps : ROW1(top), MCB No. 8	0.1	
9	GSB EXT 3 : ROW1(top), MCB No. 11	0.2	
10	GSB rack-3(EB2) : ROW2(Bottom), MCB No. 1	4.8	
11	GSB rack-2(EB2) : ROW2(Bottom), MCB No. 2	7.6	
12	GSB rack-3(EB3) : ROW2(Bottom), MCB No. 3	3.5	
13	Lamps : ROW2(Bottom), MCB No. 8	0.2	
	Grand Total	39.7*	

: Maximum on this day with current usage.
 * : Current varies during system use.

Note : As per UPS outputs, UPS2's 56% of 20KVA and UPS3's 64% of 12.5KVA ie. 11.27KVA & 8.0 KVA respectively. So total power consumption by GSB system is 19.27 KVA ie 15.416 KWatts .

Conclusions : So GWB & GSB respectively consumes a power of ~12.5 KW (15.6 KVA) and ~15.5 KWatts (19.3 KVA). And total power consumption in the correlator room is ~ 28 KWatts or 35 KVA (15.6 + 11.27 + 8.0 = 35 KVA)

If Power Factor is 0.8, then total power consumption by GSB+GWB system is : 28.0 KW ie 35 KVA.

D. GWB System Integration.

Integration of 30 antenna GWB system started with procuring 6 racks of Height x Width x Depth – 2065mm (42U+4.45 U) x 600mm x 1200mm from Jyoti Tech Industries, Rabale, Navi Mumbai. The maximum usable space is HxWxD – 1822.5mmx495mmx710mm.

While the racks getting customized at GMRT, the process of acquiring the material/units and cables required to accomplish the integration of 30 antennae GWB system was in progress. Once these works completed, we started the integration of racks one by one.

We completed intergration of 3 racks , which can work as 16 antennae GWB system was moved inside the correlator room and started testing the same for about 30 days till half yearly maintenance period. During this period of time, the required modifications done in the software and started testing the 30 antenna system (old 16 antenna and new 16 antenna). This gave us an opportunity to modify the software for the complete 30 antenna GWB system, creating the SOPs along with testing, apart from actual load test on the UPS and AC plant units. At the same time modifcaiton and integration of another 3 racks also completed.

Once all the 6 racks are inside the correlator room, decommissioned the existing 16 GWB system in the half height racks and moved all the units into new racks. All the 6 racks are integrated and installed in it's final location. The arrangement to suck the cool air at the bottom-front and hot air exhaust at the top-back of racks using 360cfm fans has been done. These can been respsectively called as cool air and hot air channels/aisles. Then started the testing of GWB system. Initially made sure the working of 16 antenna GWB system is back to it's original status and released for observation. Then testing of next half of 16 antenna and whole of 30 antenna tests and validation started before releasing the 30 antennae GWB system for user trials and observation.

1. Racks requirement, configuration and modifications.

i. Racks requirement :

Based on the tests and design of the GWB system, the following things are the basic requirements expected in the racks.

1. Height x Width x Depth – 2065mm (42+4.45 U) x 670mm x 1195mm

Height – Take care of room height from false floor and also it should pass through the door.

Width – Tow fans of ~350cfm can be mounted at the front / 3 fans of 100cfm at the backside + margings between fans and at the end of rack (sliding/mounting arrangement bars)

Depth – Front Door closing clearance + ~350cfm fans mounting / cool air channel + max.


Depth req. for units + Connectors / 100cfm fan mounting to suck some cool air and push the hot air up to aviod mixing / stayback of air + Back Door closing clearance.

2. Make sure the rack passes through the main door.

3. Vertical mounting arrangement for units should be in step of half a Unit ie 22.22mm. Also mounting bars should be moveable horizontaly, so that we can decide the cooling and hot air channels.

4. Mounting arrangement for Machines using sliding bars and ROACH/Switch using aluminum angles or readymade better options available.
5. Cable Routing inside the Rack (take care of cables length)
6. Cable In/Out from the Rack at Top & Bottom and Front & Back
7. Fans Mouning : ~350cfm at the Rack's front bottom to suck the cool air into the cool air channel, 100cfm at back bottom(if req.) and 100cfm at the back top to suck out the hot air from the rack's hot air channel.
8. Power Distribution Board's mounting arrangement at Rack's Backside.
9. Temperature Monitors in and around Rack.
10. Make sure Doors can be closed to maintain cool air inside and no leakages of cool air at front (if req. close the gaps between units at the bottom and top of the rack to force the cool air through the units)
11. Rubber cushion at the rack's bottom to plug the cool air leakout between false floor and rack's bottom.
12. Hot air exhaust opening at the rack's top backside center.
13. Arrangement for conneting hot air exhaust to the exhaust ducts in the roof top.

ii. Racks configuration :



<http://www.computerhope.com/jargon/num/1u.htm>

Unit Dimension (W x H x D)

1U	19" x 1.75" x 17.7"	19" x 1.75" x 19.7"	19" x 1.75" x 21.5"
2U	19" x 3.5" x 17.7"	19" x 3.5" x 20.9"	19" x 3.5" x 24"
3U	17.1" x 5.1" x 25.5"	4U : 19" x 7" x 17.8"	19" x 7" x 26.4"
5U	19" x 8.34" x 19.67"	19.1" x 8.75" x 26.4"	6U : 19" x 10.5" x 19.5"
7U	17" x 12.2" x 19.8"		

1U = 44.45mm = 1.75 inch

1 inch = 25.4mm.


iii. Racks modification :

The following modification have been done in the new racks based on the tests and design of the 30 antenna GWB system.

1. Two fans of 22mm dia., mounting arrangement with mesh in the backside centre of top cover. And cutting the fixing angles which obstructs the mounting of fans.
2. Two fans of 22mm dia., mounting arrangement with mesh in the bottom cover at front.
3. One hole of about 50mm diameter with rubber gland grommet for enter/exit of cables such as power, antenna signal, ethernet, RJ6 etc., at the rack's front-top-left (front view).
4. One hole of about 40mm diameter with rubber gland grommet for infiniband cables enter/exit at the rack's rear-bottom-left (rear view).
5. Cables Termination plate with Screen Printing of name/number of Antennae at the front top. All the antenna signal, pps & clk cables entering the rack gets terminated here.
6. Fixing of all the side plates inside the rack with grub screws.
7. Slot in the side Plate (which are at front inside of rack) for cables movement.
8. An aluminium plate to close the gap between units at the middle of rack.
9. An aluminium plate to close the gap behind the fans mounted in the bottom cover.
10. An arrangement to close the gap between the rack and false wooden floor.
11. Metal block to rack's legs (4 no's per rack) to increase the height.
12. Aluminium funnel to bring the cold air from inlet ducts to the racks. One from inlet number 5 to racks 1 & 2. Another from inlet number 4 to racks 5 & 6.


2. Units and specifications.

Nodes , Host and Control Machines :



Dell T620 Host/Node m/c.
 Max. space required :
 H x W x D = 220 x 482 x (630 + 110 cnctrs) mm's


Dell T630 Host/Node m/c.
 Max. space required :
 H x W x D = 220 x 482 x (750 + 110 cnctrs) mm's



Dell R210 1U PC for control works
 Max. space required :
 H x W x D = 42 x 442 x (395 + 15 + 60 cnctrs) mm's

Units	Size in mm	Units	Size in mm
0.5	22.22	2.5	111.125
1	44.45	4.5	200.10
1.5	66.70	5	222.25
2	88.90	9	400.20

Switch, ROACH unit, PPS/CLK unit, eth switch, Signal Generator, Monitor+KBD+Mouse, Fans, Power Extension & Distribution Boards, Cable Guide Ducts.



Sl.No.	Units/Machines/Instruments	Actual Size in mm			Remarks
		Height (Units)	Width+ (Handle)	Depth+ (Connector)	
1	Control PC Dell R210	40(1)	445(40)	395(60^)	^ Power Cord
2	Dell T620 Host/Node PC	220(5)	430(52)	665(110^)	^ Infiniband connector.
3	Dell T630 Host/Node PC	220(5)	430(52)	750(110^)	^ Infiniband connector.
4	ROACH Unit	60(1.5)	425(55)	550(60^)	^ CX4 cnctr
5	Melonox 36p Switch	44(1)	435	630(110^)	^ Infiniband connectors.
6	CLK/Trig distribution unit	70(2)	500	550(100^)	^ SMA
7	Ethernet switch	70(2)	500	550(100^)	^ RJ45

7	Monitor/KBD/Mouse	400(9)	400	400	
8	SignalGenerator/SpectrumAnalyzer/Noise Source	190 (4.5)	340	460(60 [^])	
9	Power Ext'n Board (can be mounted at backside of units).	120\$ (3)	610#	85(60 [^])*	\$ Make sure mountable at backside. # Available in many standards. * shouldn't obstacle the doors.
10	Fans (2 fans of ~360cfm)	100(2.5)	500#	250+120	# 50 mm space between & ends # Can be Extended in LR margins
11	Left margin Space from Mounting Pole	--	60	--	
12	Right margin Space from Mounting Pole	--	60	--	
13	Front Door Margin	--	--	60	
14	Back Door Margin	--	--	60	

Notes :


I Width.....

- a. Margins on left side from the mounting pole = 60mm
 - b. Max. width of the unit (fans) = 550mm. But can be Extended in LR margins
Look for ~360 cfm fans with lesser width say 220mm.... to accommodate in 600mm rack.
 - c. Margings on right side from the mounting pole = 60mm
- So Total Width required = 60 + 550 + 60 = 670mm

II Depth.....

- a. Front door closing clearance - 60mm
 - b. Front cool air channel (~360cfm fan) / Cable Duct + margin space - 250+20= 270mm
 - c. Max. Unit depth (T620 PC) – 665mm.
 - d. Connector / Cable Duct / Hot air Channel (360cfm fan) + margin space – 100+20 =140mm
 - e. Back door closing clearance – 60mm
- So Total Depth required – 60 + 270 + 665 + 140 + 60 = 1195mm

3. Units placement in the Racks.



gwbcorr node machines are Dell T620/T630.
 .100 n/w eth. s/w. at rear side of clk/trig. unit in each rack.

host m/c's are Dell T620/T7500.

.4 n/w eth. s/w. at rear side of .100 n/w eth s/w.

host m/c's are Dell T620/T7500.

GWBunitsInRacks.fig
 IMH 10/07/2017.

The Units placement in the Racks is done by keeping in mind :

1. Minimum inter rack cables movement.
2. Cables (infiniband and ethernet) from 5th rack will go to T620/T630 's in the racks 1 to 4. So it is placed in between the racks.
3. By using PPS/CLK units in each racks minimizes the inter rack PPS/CLK cables.
4. Using ROACH units and Nodes required for 8 antennae in the same rack, will avoid inter rack CX4 cables movement. This is also necessary due to maximum 5 meter length of CX4 cables.
5. Best utilization of space with almost equal power consumption from all racks.

4. Racks placement in the correlator room.

The Racks placement in the Correlator Room is done by keeping in mind :

1. Cool Air inlets and Exhaust ducts are near by. Usage cool air inlets 1, 4 & 5 fully and 2nd partially if required and use exhausts 2,5 & 9.
2. Rack doors opening/closing space.
3. Man-material movement space.
4. Cables movement between racks. Cables (infiniband and ethernet) from 5th rack will go to T620/T630 's in the racks 1 to 4. So it is placed in between the racks. Cables in/out will be only from top. This avoids cool air leakage at the bottom.
5. Space for packetised correlator and other racks.
6. Best utilization of space and space for future expansions.

The following table compares the various proposals for GWB racks placement in the correlator Room.

***Requirements/Features :** Noproblem=Excellent(5) & Difficult=(1)

1. Racks/Material/Man movement through door and inside the room.
2. Access of input signal panel. Noproblem=Excellent(5) & Difficult=(1)
3. Shifting of existing set-up. NotRequired/Easy=Excellent(5) & Difficult=(1)
4. Length of input signal cables. Less=Excellent(5) & More=poor(1)
5. Space for feature expansion. More=Excellent(5) & Less=poor(1)
6. Accessibility of cool air inlet ducts. Near/easy=Excellent(5) & Away/difficult=(1)
7. Accessibility of hot air outlet ducts. Near/easy=Excellent(5) & Away/difficult=(1)

Proposal#	*Requirements / Features.							Average1\$	Average2\$
	1	2	3	4	5	6	7		
1	5	5	5	3	5	4	5	4.25	4.4
2	5	4.5	3(^1)	5	5	4	4	4.50	4.2
3	4	4.5	4.5(^2)	3	4	4	5	4.00	4.1
4	5	5	5	3	5	4	4	4.00	4.2
5	5	4.5	3(^3)	5	4	4	4	4.25	4.0
6	4	5	2(^4)	4	3	5	5	4.25	3.8

Agerage1\$: This is the average of Requirements/Features points 4 to 7 only. Ignored 1 to 3, because they are not so important technically. This needs group debate (which point among 4 to 7 carries more weightage! & there is scope for revision of marks).

Agerage2\$: This is the average of Requirements/Features points 3 to 7 only. Eventhough point 3 is non technical, still it may needs to be considered.


(^1) : Removing of existing GWB3 & moving of PKTZ+ racks by one tile is required.

(^2) : Removing of existing GWB3, if we use 6th rack.



(^3) : Removing of existing GWB3 & moving of PKTZ+ racks by one tile is required.

(^4) : Removing of existing GWB3 & PKTZ+ racks completely (or moving to other location)


Proposal 1 :




Proposal 2 :



Hot Air Outlet Ducts
Total 10 Ducts @ Roof Top



Cool Air Inlet Ducts
Total 6 Ducts Under False Floor





Wooden False Floor block




Total 9*16=144 Blocks.

Proposal 3 :




Racks
Width : 600mm
Depth : 1200mm

Hot Air Outlet Ducts
Total 10 Ducts @ Roof Top



Cool Air Inlet Ducts
Total 6 Ducts Under False Floor





Wooden False Floor block




61 cms
Total 9*16=144 Blocks.


Proposal 4 :



Hot Air Outlet Ducts
Total 10 Ducts @ Roof Top



Cool Air Inlet Ducts
Total 6 Ducts Under False Floor



Wooden False Floor block



Total 9*16=144 Blocks.

5. Cool air utilization in the correlator room

Two cold air ducts are running parallel to each other from the AC plant room to the correlator room under ground. Each duct has 3 vents of 28 sq.cms in the correlator room. For the sake of identification they are numbered as 1 to 3, those are right side of the room entrance door and 4 to 6, those are left side. Vent number 3 is used to feed the cold air to racks 3 & 4 and vent number 6 is used for racks 1 and 2 of GSB system through the ducts placed below the false floor, from vents to the bottom of the racks. 2 fans of 360 cfm each are placed in the bottom of rack's front, in all the racks to draw the cold air into the racks from this duct cum tray below it.

GWB racks 1 & 2 gets cold air from the vent number 5 and racks 5 & 6 from the vent number 4 through the ducts placed below the false floor from vents to the bottom of racks. Here this duct is divided from vent to racks to split the air between two racks by half. Here also 2 fans of 360 cfm each are placed in the bottom of rack's front in all the racks to draw the cold air into the racks from the duct below it. Here duct directly opens below the fans.

GWB racks 3 & 4 respectively called as host(recording) and host(monitored) are getting air from vent number 1 & 2, but without any duct between them.

The gap between the front door and the units is called as cold air aisle and the space between the rear door and unit's back end as hot air aisle. The cold air coming out from each vent is about 1000cfm. About 500cfm is drawn into the racks by using 2 fans of 360cfm.

The heat generated by a GWB rack (number 1,2,5 or 6) is 32,180 calories/sec., which draws a current of 12.2amps ie $P=0.8 \times 12.2 \times 230=2245$ watts. 280 cfm of cool air is sufficient to takeout the heat of 2245 watts ie 32,180 calories/sec., with a temperature difference of 15DegCel between the inlet cool air and exhaust hot air. For every 1000 watts ie 14,400 calories/sec., about 125 cfm of cold air is necessary to dissipate the heat with a temperature difference of 15DegCel.

Total heat generated by a 30 antenna GWB system is about 1,80,000 calories/sec., which draws a current of 61amps ie 12,500 watts. 2 cold air inlets of 1000cfm are required. If cold air from cold air inlets is around 600cfm, then 3 inlets will be required to take this heat.

Total power consumption by GSB+GWB system is : 28.0 KW (35 KVA) ie about 4,00,000 calories/sec.,

Use the calc provided with this document for automatic calculations "auto_calc1.ods".

6. Bill of material.

Sl.No.	Items	Qty Required	Qty (20%) Spare	Total Required	Remarks
1	Racks 42U and 1200mm depth std.,	06	01*	06	GWB Racks
2	Dell R210 powerededge 1U PC	01	01*	02	Control PC
3	Dell T620/T630 Node machines	16	01#	17	
4	Dell T620 Host machines	03	01#	04	
5	K20/K40 GPU Cards	32	06	38	
6	Myricom 10Gbe Single Port cards	32	06	38	
7	Mellanox Infiniband NIC Cards	19	04	23	
8	Mellanox 32p Switch	01	01*	02	
9	ROACH Units	32	06	38	
10	ADC Cards	64	13	77	
11	CLK/Trig distribution Units	04+01	01#	06	1 is the master unit.
12	Signal Generator	01	01*	02	
13	DSO	01*	00	01	
14	SpectrumAnalyzer	01*	00	01	
15	1Gbps ETH switches	06	01*	07	
16	Power Extension Boards (10 sockets)	18	03*	21	
17	Cooling Fans 360 CFM	12	03	15	
18	Cooling Fans 100 CFM	10	05	15	
19	Monitor	01	01*	02	
20	Key Board	01	01*	02	
21	Mouse	01	01*	02	
22	Cables Routing Duct 60x65	20	01	21	Hadles ~50cables of CX4 dia.
23	TNC to SMA Cables – 5 mtrs	60	12	72	Input to ADC's.
24	CX4, 5 mtr Cables	64	13	77	ROACH to Nodes.
25	Infiniband Cables	19	04	23	Nodes/Hosts to Infiniband s/w
26	Ethernet Cables (5 mtr)	62	12	74	Switch to Nodes/ROACH
27	Ethernet Cables (>20mtr)	08	01	09	Network to Switches
28	Power Cords	83	17	100	2 for Dell T series and 1 for all
29	Aluminum angles				For ROACH units
30	Aluminum angles				For PPS-CLK unit/Eth s/w, SignalGenerator/ Noise Source/ Monitor /HDD/ temperature monitoring machines etc..

Note : Spare quantity taken as 20% , except costly items like Rack, Dell T620 PC's & 32pSwitch.

*** Spare may be shared with other activities. # Hot spare should be in the working Rack.**

7. Electrical connections.

UPS 1 of 20 KVA has been used to feed the electrical power to this GWB 30 antenna system. Each rack has 3 power extension boards each having 10 sockets at top, middle and bottom of the racks. The first 3 MCB's of top row feeds electrical power to first 3 racks and first 3 MCB's of bottom row feeds electrical power to next 3 racks. Each rack gets 2 copper cables of dia. 2.5 sq.mm from the 25amps MCB at UPS1 power distribution box inside the correlator room near the main entrance door. These two copper cables are connected to the top and bottom power extension boards in the racks.

The middle power extension board is now unused. It is reserved for getting the electrical power from another UPS. So in the event of power cut from the UPS1 due to any reason, the node/host machines will get power from this machine, because these Dell T620/T630 machines have provision of automatic switch over between the two AC power inputs. Also to maintain atleast one of the two fans at the front bottom and backside top of the racks is working, one of the two fans will get power from the middle power extension board ie from second UPS.

8. Inter rack connections.


All racks have 50mm diameter hole at the rack's top left (front view) and about 40mm diameter hole at the rack's rearside, bottom, left (rear view) in all the racks for inter rack cable movements listed below. Only infiniband cables enter/exit through the rack's rear bottom hole.

Rack#	Cables entering the rack	Cables exiting the rack
1 & 2	Electrical power cables – 2 nos. Antenna signals from Rx system – 16 nos*, Clock & PPS signals from rack 4 – 1 each, .4 n/w & .1001 n/w eth cable -1 no. each, & Infiniband cables – 4 no's** from rack 3.	
5 & 6	Electrical power cables – 2 nos., Antenna signals from Rx system – 16 nos*, Clock & PPS signals from rack 4 – 1 each, .4 n/w & .1001 n/w eth cable -1 no. each, & Infiniband cables – 4 no's** from rack 3.	
3	Electrical power cables – 2 nos., .4 n/w eth cable from core s/w – 4 no's., Infiniband cables to nodes/host m/c's in all racks ie. 1 to 6 – 1 each**.	.4 n/w eth cable to all other racks -1 each for debugging/testing purpose. .100 n/w eth cables to racks 1,2,5 & 6 – 1 each to .100 n/w distribution s/w in respective racks.
4	Electrical power cables – 2 nos., .4 n/w n/w eth cable -1 no.,10MHz ref. Signal to 800MHz main clock generator Hittite instrument from Rx room – 1 no., & Infiniband cables – 4 no's** from rack 3.	PPS and Clock signals to racks 1,2,5 & 6 – 1 each to clk & pps distribution units in respective racks.

** - Infiniband cables (orange colour, thin cables) are entering/exiting the rack through the holes made at the rack's rear bottom, left side.

9. Intra rack connections.

The following image divulge the details of cables movement between units with in the racks 1 to 6.



10. Integration of system.

The racks were modified and all the required units and components were acquired, integrated the 16 antenna GWB system in the 3 racks. Tests were carried out along with the existing 16 antenna GWB system, which was integrated in the racks available with us after dismantling the old hardware correlator system. This gave us an opportunity to modify the software for the complete 30 antenna GWB system, creating the SOPs along with testing, apart from actual load test on the UPS and AC plant units.

The 30 Antenna GWB system has been integrated in it's final position in the correlator room and necessary tests have been carried out to confirm it's working. The 30 antennae GWB system has 6 racks. Racks 1, 2, 5 & 6 are integrated with 4 numbers of Dell T620 or Dell T630 as compute nodes with 2 numbers of K20/K40 nVIDIA GPU cards. At the top of the rack, one PPS/Clock distribution unit & 4 numbers of ROACH units with 2 iADC cards are integrated. Rack 1 has, one additional T630 machine for raw voltage recording.

The rack number 3 has five host machines (recording). Also has control 1U machine and two switches for .4 and .100 ethernet network distribution between units and racks and one 36 ports infiniband switch for high speed data transfer between the compute and host nodes.

The rack number 4 has five host machines (monitoring) 800Mhz, +15dbm main clock generator synchronized with the 10MHz signal, clock and pps distribution units to distribute the same to racks numbers 1, 2, 5 & 6. And has one .4 network ethernet switch for host nodes in the same rack. Also has computers for temperature monitoring.

Few snaps of the 30 antenna GWB system.



Image 1 : 30 Antenna GWB system integrated in 6 racks..



Image 2 : Back view of the 30 Antenna GWB system with outlet hot air duct above the racks.

11. SOP's and Testing.

Rack number 1 processes the polarization 1 signals from 14 Central square antenna's, E02 & E03. Rack number 2 processes the polarization 2 signals from the same antenna's. Rack number 5 & 6 respectively processes the polarization 1 & 2 signals from the antenna's E4 to E6, South & West arm and also 2 spares.

The 30 antennae GWB system has 6 racks. Racks 1, 2, 5 & 6 are integrated with 4 numbers of Dell T620 or Dell T630 as compute nodes with 2 numbers of K20/K40 nVIDIA GPU cards, two Myricom 10Gbe Single Port cards and one Myricom 10Gbe Single Port card. At the top of the rack, one PPS/Clock distribution unit & 4 numbers of ROACH units with 2 iADC cards are integrated. Rack 1 has, one additional T630 machine for raw voltage recording.

The rack number 3 has five host machines (recording) Dell T620/T630 with one Myricom 10Gbe Single Port card. Also has control 1U machine and two switches for .4 and . 100 ethernet network distribution between units and racks and one 36 ports infiniband switch for high speed data transfer between the compute and host nodes.

The rack number 4 has five host machines (monitoring) Dell T620/T630 with one Myricom 10Gbe Single Port card, Hittite instrument for main clock generator 800Mhz, +15dbm synchronized with the 10MHz signal and clock & pps distribution units to distribute the same to racks 1, 2, 5 & 6. And also has one .4 network ethernet switch for host nodes in the same rack and computers for temperature monitoring. **35**

E. Conclusion

A. Theoretically each inlet gives 1000CFM of cool air. So we need 2.68 cool air inlets to absorb the heat generated by GWB system of 21,500 Watts (3,08,185 calories/minute). But practically, with 3fans of 100cfm each to suck the cool air into the al. cage, we need 5.38 cool air inlets. This is double the theoretical requirement. So we have to find out the reasons, which could be as follows ;

1. Actual cool air spilt for the correlator room may not be 6000 CFM.
2. There may be leakages between the AHU and correlator room inlets.
3. May be considerable leakages at the bottom of the rack.
4. May be adjustment of locations of the heat load is required in the rack, in order to utilize the cool air efficiently.
5. May be adjustment of locations of the input/output thermometers is required to findout the actual volume of the cool air, which may be more than 482 CFM.
6. If possible and not harmful to the system, increase the humidity of the cool air (decrease the temperature of the cool air coming out of the inlets).

B. We found the following things are useful in utilising the cool air efficiently.

1. We have replaced the 3 fans of 100cfm each to suck the cool air into the al. cage by 2 fans of 600cfm at 2' height in the al. cage.
2. Made sure the cool air entered in the rack, shouldn't leakout.
3. And also took care of no obstacles in the cool air flow towards the exit in the rack.

Enentough the rack is kept 5 feet away from the cool air duct and without any aluminium cage/duct to bring the cool air from the inlet(setup No. 3a), we got a averaged temperature difference of 5.4 degCel.

If we move these fans from the al. cage to the bottom of the rack and keep the slot in the al. cage @ 2' height open, then the temperature difference increases to 9.21 degCel.

This temperature increases by around 1 degCel, if we put 3 fans of 100cfm each at the open slot in the al. cage!

If we take maximum of these ie 9.21 DegCel, then the volume of cool air from the outlet is 812cfm.

So we need 3.19 inlets of 1000cfm cool air to dissipate 21,500KW heat from GWB system.

Appendices :

1 Auto calculator

Usage : "auto_calc1.ods " is an auto calculator as copy-pasted below, is for calculating the output parameters by providing input parameters.

User Parameters :	INPUTS	Output Parameters	OUTPUTS
PowerConsumption in Watts -->	12500	Total Heat Energy in calories/minute -->	1,79,177
Difference in Temperature -->	15	Heat Absorption of Cool Air cal/min -->	69,042
Volume of Cool Air in ft ³ /inlet in corr. room-->	600	Number of cool air inlets required..	2.60
Heat to be absorbed in watts -->	2,245		
Temperature Difference in deg. Cel.permitted -->	15.00	Volume of Cool Air in ft³ to absorb the heat :	280

Constant Parameters :	Constant Values	Intermittent Calculation Parameters :	int'nt. results
1 Joule equal to --> Calories	0.2389029576	Volume of Cool Air in mtr ³ -->	16.992
1 Cubic feet equal to --> Cubic mtr	0.02832	Mass of cool air in kg/minute -->	19.178304006
Air Density kg/mtr ³ @ 25dC & 1 Pascal	1.128666667		
Specific Heat of Air cal/kgdC @ 20dC & 1 Pascal	240		

Tables :

Total Heat Energy in Cal./min.

For 1000 watts of Power Consumption -->	14,334
For 1500 watts of Power Consumption -->	21,501
For 2000 watts of Power Consumption -->	28,668
For 2500 watts of Power Consumption -->	35,835
For 3000 watts of Power Consumption -->	43,003
For 3500 watts of Power Consumption -->	50,170
For 4000 watts of Power Consumption -->	57,337
For 4500 watts of Power Consumption -->	64,504
For 5000 watts of Power Consumption -->	71,671

Volume of Cool Air in ft³ @1KW heat if :

Temperature difference of 3 deg. Cel.	1,398
Temperature difference of 3.5 deg. Cel.	1,199
Temperature difference of 4 deg. Cel.	1,049
Temperature difference of 4.5 deg. Cel.	932
Temperature difference of 5 deg. Cel.	839

Heat Absorption of Cool Air in cal./min.

For 1000ft ³ /min. Cool air	
For Temperature difference of 1 deg.Cel.	4,603
For Temperature difference of 1.5 deg.Cel.	6,904
For Temperature difference of 2 deg.Cel.	9,206
For Temperature difference of 2.5 deg.Cel.	11,507
For Temperature difference of 3 deg.Cel.	13,808
For Temperature difference of 3.5 deg.Cel.	16,110
For Temperature difference of 4 deg.Cel.	18,411
For Temperature difference of 4.5 deg.Cel.	20,713
For Temperature difference of 5 deg.Cel.	23,014
For Temperature difference of 5.5 deg.Cel.	25,315
For Temperature difference of 6 deg.Cel.	27,617
For Temperature difference of 6.5 deg.Cel.	29,918
For Temperature difference of 7 deg.Cel.	32,220
For Temperature difference of 7.5 deg.Cel.	34,521
For Temperature difference of 8 deg.Cel.	36,822
For Temperature difference of 8.5 deg.Cel.	39,124
For Temperature difference of 9 deg.Cel.	41,425
For Temperature difference of 9.5 deg.Cel.	43,727
For Temperature difference of 10 deg.Cel.	46,028

2 Experiment setup details

The following setups were done with the help of mechanical and electrical sections. These setups were used to study the effects of cooling over varying temperature under different conditions like when the rack is placed over the inlet cool air duct or 5 feet away from it and so on.... A total of 8 setups were created to study the possible conditions to make out the rise in temperature at the output over input ie difference in temperature of the air entering the rack and exiting the rack.

Setup 1 : 42U Rack directly on the cool air inlet in the corr room with all the leakages at the bottom closed. The cool air enters the rack from the front bottom opening and enters the aluminium cage through a window provided in the cage at a height of about 2 feet. One thermometer(T1) and two temperature sensors (S2 & S3) are present at this opening to measure the inlet temperature. Inside the al. cage about a feet high 4 hellogen (with seperate ON-OFF switches in the two extension boards having current carrying capacity of 16amps. These two extension boards are getting power from MSEB metal MCB box through 25amps MCB) lamps of 1 KW each are mounted. Some 3 feet above these lamps there is window in the al cage at the backside for heated air to exhaust. At this poist also one thermometer (T2) and two sensors (S4 & S5) are mounted. Sensor S1 is outside and near to this rack.

Rabbit card gets input on pin numbers 1 to 5 on 64pin FRC male connector from sensors S1 to S5 respectively. +11 volts power has been given to this rabbit card as well all to all temperature sensor cards. An ethernet cable with ip 192.168.4.152 has been connected to this rabbit card for web based monitoring of temperature.

Setup 2 : setup 1 with 3 fans of 100cfm each, mounted at the height of about 2 feet front side, to suck air in the aluminium cage.

Setup 2a : setup 2 with 2 fans of 600cfm each, mounted at the height of about 2 feet front side, to suck air in the aluminium cage. This is done with and without aluminium plate in al. cage to abstruct the air.

Setup 3 : setup 1 & 2 with whole setup moved about 5 feet away from cool air inlet duct. Cool air brought to the rack's inlet using aluminium sheet enclosure underneath the false flooring.

Setup 3a : setup 3 with 2 fans of 600cfm each instead 3 fans with 100cfm each and without al. enclosure to bring the cool air to rack.This is done with and without an aluminium plate in the al. cage in the rack, to be an obstacle in the air flow.

Setup 3b : setup 3a with 2 fans of 600cfm each, moved to bottom of the rack with opening @ 2' height. This is done with and without an aluminium plate in the al. cage in the rack, to be an obstacle in the air flow.

Setup 4 : setup 3 without fans to suck the cool air in the aluminium cage at 2 feet height.

Setup 5 : setup 3 without aluminium sheet enclosure underneath the false flooring to bring the cool air from the inlet duct to the rack and with fans to suck the air in the aluminium cage at 2 feet height.

Setup 6 : setup 5 but without fans to suck the cool air in the aluminium cage at 2 feet height.

Setup 7 : Rack without any modifications (aluminium cage in the rack removed). Kept 5 feet away from the cool air inlet duct. Input temperature monitoring about 2 feet high at the frontside. Four hellogens of 1 KW each mounted at the centre of the rack. And output temperature monitoring at the top of the rack's rear side.

Setup 8 : Rack without any modifications (aluminium cage in the rack removed). Kept over the cool air inlet duct. Input temperature monitoring about 2 feet high at the frontside, where cool air blows in the rack's bottom. Four hellogens of 1 KW each mounted at the centre of the rack. And output temperature monitoring at the top of the rack's rear side.

**T – Thermometer readings average. & S – Temperature Sensors readings average in Deg. Cel.
LH – Left Hand side RH – Right Hand side (from back) F- Front of rack B – Back of rack.**

3 Summary of Daily readings

Setup No.	Measuring Instrument	Average temp. readings for				Max. output temp. for 4KW	Temp. Sensor minus Thermometer readings.
		1KW	2KW	3KW	4KW		
I	Themometer	3.0	6.6	11.2	--	20.0	1.2
	Temperature Sensor	4.2	8.2	12.2	--		
II	Themometer	2.6	6.3	9.0	11.7	22.5	2.2
	Temperature Sensor	4.3	8.2	11.7	14.2		
IIa	Themometer/TempSe	6.23	8.89	with al. plate		16.00	2.26
	Themometer/TempSe	3.50	6.06	w/o al. plate		17.00	2.56
III	Themometer	2.8	7.3	12.5	14.8	25.5	2.6
	Temperature Sensor	5.3	10.0	14.9	17.6		
IIIa	Themometer/TempSe	9.21	9.23	with al. plate		20.00	0.02
	Themometer/TempSe	6.12	5.33	w/o al. plate		21.00	-0.79
IIIb	Themometer/TempSe	10.64	13.26	with al. plate		20.50	2.62
	Themometer/TempSe	10.82	12.84	w/o al. plate		20.00	2.02
IV	Themometer	3.5	10.0	14.1	18.5	28	2.8
	Temperature Sensor	6.4	12.6	17.1	21.4		
V	Themometer	4.8	9.5	11	18.4	33	-3.0
	Temperature Sensor	3.8	6.5	9.3	12.1		
VI	Themometer	8.0	18.2	24.8	31.7	46	1.8
	Temperature Sensor	10.5	20.0	26.8	32.7		
VII	Themometer	-5.2	-3.2	-1.3	-1.1	31.5	1.9
	Temperature Sensor	-0.8	-1.3	-2.3	+1.2		
VIII	Themometer	-2.2	-3.1	-3.1	-2.8	9.0	1.0

Note : Thermometer readings are considered.

4 Average of Daily readings

SETUP : 1

42U Rack directly placed on the cool air inlet in the correlator room with all the leakages at the bottom closed. Aluminium cage with cool air in and hot air out and load in the centre of the cage.

Date	Difference in Temperature Readings		Heat load of KW's	Time	Remarks
	T	S			
10/10/2014	4	4	1	12 - 17	Readings every half an hour
11/10/2014	7	8.5	2	11 - 17	“
13/10/2014	3	4	1	10 - 17	“
14/10/2014	8	8.5	2	10 - 17	“
15/10/2014	3.5	4	1	10 - 17	“
16/10/2014	2.5	4.5	1	10 - 17	“
18/10/2014	3	4.2	1	10 - 17	“
20/10/2014	2	4	1	10 - 15	“
21/10/2014	3	4.5	1	10 - 12	LH-1 every 5 min.
	10.5	11.5	3	12 - 13	LH-1 + RH-2 “
22/10/2014	6	8	2	10 - 12	LHB + RHB every 10 min.
	5.5	8	2	12 - 13	LHF + RHF “
	12	13	3	14 - 15	LH-2 + RH “

Average Readings in degCel.

	1KW	2KW	3KW	4KW
Thermometer	3	6.6	11.2	18
Temp. Sensors	4.2	8.2	12.2	21

Conclusions : Temperature Sensor results are about 1.2degCel. more than the Thermometer readings. And maximum output temperature for 4 KW is about 20 degCel.

SETUP : 2

setup 1 with 3 fans of 100cfm mounted at the height of about 2 feet front side, to suck air in the aluminium cage.

Date	Difference in Temperature Readings		Heat load of KW's	Time	Remarks
	T	S			
28/10/2014	2	4.2	1	10:00 - 11:40	LHB every 10 min.
	8.5	9	2	11:45 - 13:00	LHB + RHB “
	10	12.5	3	14:10 - 15:30	LH-2 + RH “
	13	15.5	4	15:40 - 16:40	All “
29/10/2014	11	13.5	4	09:40 - 11:30	All every 10 min.
	10	12.5	3	11:40 - 13:00	LH-2 + RHF “
	7.5	9.5	2	14:20 - 15:20	LHB + RHB “
	2.5	4.5	1	15:55 - 17:10	LHB “

30/10/2014	2	4.2	1	09:45 - 10:40	LHF	every 10 min.
	2	4	1	10:50 - 11:45	RHF	“
	4	5.2	1	12:00 - 12:55	RHB	“
	2.5	4	1	14:10 - 15:00	LHB	“
	5	7	2	15:30 - 16:10	LH-2	“
	5.5	8	2	16:20 - 17:20	RH-2	“
31/10/2014	6.2	7.7	2	09:50 - 11:30	LHF+RHB	every 10 min.
	5.2	7.7	2	11:35 - 14:20	LHB+RHF	“
	7.2	10.3	3	14:25 - 16:40	LH-2+RHF	“
31/10/2014	11	13.5	4	09:45 - 16:00	All	every 10 min.
26/05/2015 Page 19	8.0	10.5	4	14:30 - 16:50	All	every 10 min. w/o al. plate obstacke in the al. cage.

Average Readings in degCel.

	<u>1KW</u>	<u>2KW</u>	<u>3KW</u>	<u>4KW</u>
Themometer	2.6	6.3	9.0	11.7
Temp. Sensors	4.3	8.2	11.7	14.2

Conclusions : Temperature Sensor results are about 2 degCel. more than the Themometer readings. And maximum output temperature for 4 KW is about 22.5 (1/11/2014@14:50hrs) Alos noted a decrease of temperature by 3 degCel if remove the al. plate in the al. cage.

SETUP : 2a

setup 2 with 2 fans of 600cfm mounted at the height of about 2 feet front side, to suck air in the aluminium cage.

Date	Difference in Temperature Readings		Heat load of KW's	Time	Remarks
	<u>T</u>	<u>S</u>			
03/06/2015 Page 20	6.23	8.89	4	12:40 - 17:00	All every 10 min. with al. plate obstacke in the al. cage.
05/06/2015 Page 20	3.50	6.06	4	10:20 - 17:00	All every 10 min. w/o al. plate obstacke in the al. cage.

SETUP : 3

setup 1 & 2 with whole setup moved about 5 feet away from cool air inlet duct. Cool air brought to the rack's inlet using aluminium sheet enclosure underneath the false flooring.

Date	Difference in Temperature Readings		Heat load of KW's	Time		Remarks
	T	S				
07/11/2014 Sheet 1	6.8	9.3	2	15:20 - 17:10	RHB+RHF	every 10 min.
10/11/2014 sheet 2	16.0	17.82	4	10:00 - 13:00	All	“
11/11/2014 sheet 3	12.72	15.25	3	14:15 - 17:10	LH-2+RHB	“
12/11/2014 sheet 4	2.28	5.12	1	10:00 - 14:20	LHF	“
13/11/2014 sheet 5	6.50	8.74	2	14:50 - 17:15	RH-2	“
14/11/2014 sheet 6	6.19	9.36	2	10:00 - 14:20	LH -2	“
15/11/2014 sheet 7	7.00	10.08	2	14:10 - 15:15	LHB+RHF	“
16/11/2014 sheet 8	7.50	10.54	2	09:50 - 14:35	LHF+RHB	“
	1.93	4.04	1	14:40 - 17:10	RHF	“
	3.93	6.13	1	10:20 - 14:40	RHF	“
	2.81	5.53	1	14:45 - 17:20	LHB	“
	3.30	5.95	1	10:10 - 11:30	RHB	“
	9.64	12.02	2	11:35 - 14:20	LHB+RHB	“
	12.33	14.63	3	14:30 - 15:50	LHB+RH-2	“
	13.70	16.38	4	15:55 - 17:20	All	“
	14.79	18.67	4	09:25 - 20:10	All	“

Average Readings in degCel.

	1KW	2KW	3KW	4KW
Themometer	2.8	7.3	12.5	14.8
Temp. Sensors	5.3	10.0	14.9	17.6

Conclusions : Temperature Sensor results are about 2.5 degCel. more than the Themometer readings. And maximum output temperature for 4 KW is about 25.5 (16/11/2014@12:00hrs sheet no. 8 of temp_readings.ods file.)

Setup 3a : setup 3 with 2 fans of 600cfm each instead 3 fans with 100cfm each.

Date	Difference in Temperature Readings		Heat load of KW's	Time	Remarks
	T	S			
08/06/2015 Page 21	6.12	5.33	4 All	15:10 - 17:10	every 10 min. w/o al. plate obstacke in the al. cage.
09/06/2015 Page 21	9.21	9.23	4 All	10:00 - 17:10	every 10 min. with al. plate obstacke in the al. cage.
16/06/2015 page 22	9.89	12.74	4 All	14:40 - 17:10	with plate “

Setup 3b : setup 3a with 2 fans of 600cfm each moved to bottom of the rack with opening @ 2' height.

17/06/2015	10.64	13.26	4	All	10:10 - 17:10	every 10 min.
Page 22						with al. plate obstacke in the al. cage.
18/06/2015	10.82	12.84	4	All	10:00 - 17:10	every 10 min.
Page 23						w/o al. plate obstacke in the al. cage.

SETUP : 4

setup 3 but without fans to suck the cool air in the aluminium cage at 2 feet height.

{Sheet number 13 & 14 in the temp_readings.ods file}

Date	Difference in Temperature		Heat load of KW's	Time		Remarks
	Readings					
	T	S				
26/12/2014	18.00	21.30	4	11:50 - 15:30	All	every 10 min.
Sheet 13	14.80	17.69	3	15:40 - 17:10	LH-2+RHF	“
27/12/2014	11.54	13.33	2	09:55 - 12:00	LHB+RHB	every 10 min.
Sheet 13	04.53	06.61	1	12:10 - 16:10	LHB	“
	18.33	21.15	4	16:20 - 21:00	All	
28/12/2014	13.44	16.48	3	12:20 - 15:00	LHF+RH-2	every 10 min.
Sheet 14	08.57	11.99	2	15:10 - 16:30	LHF+RHF	“
	02.50	06.15	1	16:40 - 20:30	RHF	“
29/12/2014	19.21	21.70	4	10:10 - 16:40	All	every 10 min.
Sheet 14						

Note : In this setup when bottom of the rack wasn't packed properly, so cool air was passing there. The average readings were about 1 to 4 degrees higher than the above mentioned (Readings in the Sheet number 9 of temp_readings.ods file) readings for 1KW to 4KW load resp.. Above readings are taken again after packing the rack bottom with the floor.

Average Readings in degCel.

	<u>1KW</u>	<u>2KW</u>	<u>3KW</u>	<u>4KW</u>
Themometer	3.5	10.0	14.1	18.5
Temp. Sensors	6.4	12.6	17.1	21.4

Conclusions : Temperature Sensor results are about 1.2degCel. more than the Themometer readings. And maximum output temperature for 4 KW is about 28.0 (26,27,29/11/2014 sheets 13 & 14)

SETUP : 5

setup moved 5 feet away from the inlet cool air duct, without aluminium duct between cool air inlet and rack but fans to suck air at the aluminium cage present.

{Sheet number 11 in the temp_readings.ods file}

Date	Difference in Temperature Readings		Heat load of KW's	Time		Remarks
	T	S				
26/11/2014	11.90	08.23	3	09:50 - 11:30	LHF+RH-2	every 10 min.
Sheet 11	09.60	06.86	2	12:00 - 13:00	LHF+RHF	“
27/11/2014	17.95	11.33	4	11:30 - 13:00	All	every 10 min.
Sheet 11	06.45	05.35	1	14:20 - 16:00	LHB	“
	09.20	06.14	2	16:30 - 17:10	LHB+RHF	“
28/11/2014	18.31	11.37	4	10:20 - 12:50	All	every 10 min.
Sheet 11						
31/12/2014	18.73	12.17	4	10:30 - 16:30	All	“
sheet 16						
01/01/2015	10.14	10.44	3	10:00 - 11:30	LH-2+RHB	“
sheet 16	9.63	06.44	2	14.15 - 16:00	LHF+RHB	“
02/01/2015	3.22	02.18	1	10:10 - 14:10	RHF	“
sheet 16	17.79	12.38	4	15:00 - 16:00	All	“
03/01/2015	19.14	13.14	4	10:00 - 12:10	All	“

Note : In this setup Thermometer reading are higher than the sensor readings!

	Average Readings in degCel.				Max. o/p temp. 4KW	Themometer +/- Temp. Sensor
	1KW	2KW	3KW	4KW		
Themometer	4.8	9.5	11	18.4		
Temp. Sensors	3.8	6.5	9.3	12.1		

Conclusions : Temperature Sensor results are about 1 to 6 degCel. less than the Themometer readings. And maximum output temperature for 4 KW is about 33degCel (sheets 11 and 16)

SETUP : 6

setup 5 but without fans to suck the cool air in the aluminium cage at 2 feet height.

{Sheet number 12 in the temp_readings.ods file}

Date	Difference in Temperature Readings		Heat load of KW's	Time		Remarks
	T	S				
28/11/2014	08.00	10.55	1	14:30 - 16:00	LHF	every 10 min.
Sheet 12	18.70	20.61	2	16:20 - 17:00	LHF+RHB	“

01/12/2014	23.85	26.10	3	10:00 - 12:00	LHF+RH-2	every 10 min.
Sheet 12	18.18	19.96	2	12:10 - 14:50	LHB+RHF	“
02/12/2014	32.36	34.08	4	10:00 - 12:50	All	every 10 min.
Sheet 12	17.67	19.64	2	14:10 - 15:30	LH-2	“
30/12/2014	30.11	30.20	4	12:20 - 15:50	All	every 10 min.
03/01/2015	32.56	33.87	4	12:30 - 17:00	All	“
05/01/2015	25.84	27.50	3	12:10 - 17:10	LHF+RF-2	“
sheet 15						

Average Readings in degCel.

	<u>1KW</u>	<u>2KW</u>	<u>3KW</u>	<u>4KW</u>
Themometer	8.0	18.2	24.8	31.7
Temp. Sensors	10.5	20.0	26.8	32.7

Conclusions : Temperature Sensor results are about 1 to 2 degCel. more than the Themometer readings. And maximum output temperature for 4 KW is about 46 degCel. (sheet no. 12)

SETUP : 7

Rack without any modifications (aluminium cage in the rack removed). Kept 5 feet away from the cool air inlet duct. {Sheet number 17 in the temp_readings.ods file}

<u>Date</u>	<u>Readings</u>		<u>Heat load of</u> <u>KW's</u>	<u>Time</u>		<u>Remarks</u>
	<u>T</u>	<u>S</u>				
22/01/2015	-1.14	1.24	4	11:40 - 16:00	All	every 10 min.
Sheet 17						
23/01/2015	-1.26	2.27	3	10:00 - 14:20	LHB+RH-2	every 10 min.
Sheet 17	-3.22	1.27	2	14:30 - 15:50	LHB+RHB	“
	-5.25	-0.79	1	16:00 - 17:20	RHB	“

Average Readings in degCel.

	<u>1KW</u>	<u>2KW</u>	<u>3KW</u>	<u>4KW</u>
Themometer	-5.2	-3.2	-1.3	-1.1
Temp. Sensors	-0.8	-1.3	-2.3	+1.2

Conclusions : Temperature Sensor results are about 1 to 4 degCel. less than the Themometer readings. And maximum output temperature for 4 KW is about 31.5 on 22/01/2015 sheet no. 17.

SETUP : 8

Rack without any modifications (aluminium cage in the rack removed). Kept over the cool air inlet duct. {Sheet number 17 in the temp_readings.ods file}

<u>Date</u>	<u>Difference in</u> <u>Temperature</u> <u>Readings</u>		<u>Heat load of</u> <u>KW's</u>	<u>Time</u>		<u>Remarks</u>
	<u>T</u>	<u>S</u>				
24/01/2015	-2.78	-3.35	4	12:30 - 17:10	All	every 10 min.
Sheet 18						

30/01/2015	-3.17	-2.20	3	10:30 - 14:50	LHB+RH-2	“
Sheet 18	-3.21	-1.70	2	15:00 - 17:10	LHB+RHB	“
02/02/2015	-2.21	-0.50	1	10:00 - 12:00	LHF	“
Sheet 18	-3.04	-1.10	2	12:10 - 15:00	LH-2	“
	-3.14	-1.68	3	15:10 - 17:20	LH-2+RHB	“

Average Readings in degCel.

	<u>1KW</u>	<u>2KW</u>	<u>3KW</u>	<u>4KW</u>
Thermometer	-2.2	-3.1	-3.1	-2.8
Temp. Sensors	-0.5	-1.4	-2.0	-3.3

Conclusions : Temperature Sensor results are about 1.5 degCel. more than the Thermometer readings. And maximum output temperature for 4 KW is about 9.0 degCel 24/01/2015 sheet no. 18.

Conclusions :

Setup No.	<u>Temperature Difference Range, for the Heat Load of</u>				Remarks
	<u>1 KW</u>	<u>2 KW</u>	<u>3 KW</u>	<u>4 KW</u>	
1	2 – 4	5.5 – 8	10.5 – 12	not done	Thermometer
	4 – 4.5	8 – 8.5	11.5 – 13	not done	Temp. Sensors
Average	3.2	7	11.7	not done	
2	2 – 4	5 – 8.5	7.2 – 10	11 – 13	Thermometer
	4 – 5.2	7 – 9.5	10.3 – 12.5	13.5 – 15.5	Temp. Sensors
Average	3.6	7.2	9.8	13.2	
3	2 – 4	6 – 9.5	12.3 – 12.7	13.7 – 16.0	Thermometer
	4 – 6	8.7 – 12	14.6 – 15.3	16.4 – 18.7	Temp. Sensors
Average	4	8	13.8	16.2	
4	2.5 – 4.5	8.5 – 11.5	13.5 – 14.8	18.0 – 19.2	Thermometer
	6.2 – 6.6	12.0 – 13.3	16.5 – 17.7	21.2 – 21.7	Temp. Sensors
Average	4.6	10.9	15.6	19.8	
5	3.2 - 6.4	9.2 – 9.6	10.1 - 11.9	17.8 - 19.1	Thermometer
	2.2 - 5.3	6.1 - 6.8	8.2 – 10.5	11.4 – 13.1	Temp. Sensors
Average	4.3	7.8	10.0	10.4	
6	8.0	17.7 – 18.7	23.8 - 25.9	30.1 - 32.5	Thermometer
	10.5	19.6 – 20.6	26.1 - 27.5	30.2 - 34.0	Temp. Sensors
Average	9.2	19.2	25.8	32.0	
7	-5.25	-3.22	-1.26	-1.14	Thermometer
	-0.79	1.27	2.27	1.24	Temp. Sensors
Average	- 3.02	- 1.0	- 0.5	0.05	

8	-2.21 -0.50	-3.04 - -3.21 -1.10 - -1.70	-3.08 - -3.14 -1.68 - -2.20	-3.35 -2.78	Thermometer Temp. Sensors
Average	-1.35	-2.15	-2.41	-3.1	

<u>Setup#</u>	<u>with al. plate</u> <u>Ther / T.Sensor</u>	<u>w/o al. plate (inside the al. cage which obstructs the air flow)</u> <u>Ther / T.Sensor</u>	<u>Remarks</u>
2a	6.23 / 8.89	3.50 / 6.06	--
3a	9.55 / 10.98	6.12 / 5.33	--
3b	10.64 / 13.26	10.82 / 12.84	slot in the al. cage at 2' height open. This temp. diff. increases by 1 degCel., if we put 3 fans of 100cfm at open slot.

5 Daily Readings

Please refer the file temp_readings.ods attached with this report.

6 Air Flow meter User Manual



Visit the webpage :
<http://www.extech.com/instruments/product.asp?catid=1&prodid=600>

and click at the

English User's Manual
under Downloads & Software

for complete User Manual.

OR

Documents available with the Meter.

OR

file "HD350_UM.pdf" attached with this Report.

Introduction :

Congratulations on your purchase of the Extech HD350. This handheld meter measures and displays air velocity (speed), air flow (volume), ambient air temperature, and gauge/differential pressure. This meter is shipped fully tested and calibrated and, with proper use, will provide years of reliable service.