

Switch-ON SOP of Correlator System

(all Digital Backends and misc. m/c's)

Digital Backend Group Members, Date : 05/10/2018

1. GWB System :

- a. Switch ON the UPS/INPUT & Individual MCBs, if switched OFF
- b. Switch ON all the gwbh1 to gwbh10 m/c's and gwbcorr1 to gwbcorr16 m/c's in GWB rack1 to rack6.
- c. Switch ON the [ctrlpoco](#) m/c in the GWB rack3(top)
- d. Turn ON all ROACH boards by pressing the power ON-OFF switch
- e. Then Turn ON master pps distribution Unit in GWB rack4 by putting back the AC input cable
- g. Turn ON the Hitite Signal Generator (for Clock in the GWB rack4) and then set Frequency at 800MHz, Power at 20dbm and "EXT ON" using knob and button.
- h. Turn ON the Temperature monitoring machine in the GWB rack 4
- i. Make sure all switches and fans in the racks are ON/working.

2. GSB System :

- a. Switch ON the UPS/INPUT & Individual MCBs, if switched OFF
- b. Switch-ON the gsbm1 m/c in the GSB rack5. Make sure it ping from the online/astro8 m/c's from the control room.
- c. Switch-ON the gsbm2 to gsbm6 m/c's in the GSB rack5. Make sure they ping from the online/astro8 m/c's from the control room.
- d. Switch-ON node1 to node50 in the GSB rack1 to rack4. Make sure they ping from the online/astro8 m/c's from the control room and /mnt/code is mounted on each of them.
NOTE : If any node is not getting power-ON, then remove the power cord, put back & try to switch-ON. Still not, then remove the power unit at the left side(from backside), put it back & then try to switch-ON. Still not, then replace the power unit by spare unit with **SSM**.
- e. Switch-ON the N111 to N118 and CITA1 to CITA7 nodes in the GSB rack4. Make sure all are ON.
- f. Switch-ON node51 to node54 in the GSB rack6. Make sure it ping from the online/astro8 m/c's from the control room.
- g. Make sure all switches and fans in the racks are ON/working.

3. ONLINE machines (in GSB rack5 & rack6) :

Switch-ON GSB online m/c in the GSB rack5 and GWB online m/c in the GSB rack6.

4. CASPER/SERVER/Misc. m/c's in the GSB rack6 :

Switch-ON all the remaining m/c's in the GSB rack6 one by one.

5. GWBcopy/GWBmp/RFIanalysis/Misc. m/c's & Units in the rack adjacent to GWB rack1 :

Switch-ON all the m/c's and units(if any) in the rack one by one.

6. GWB II System in receiver room :

- a. Switch-ON the gwbm1, gpunode5, gpunode6 & ptpgm m/c's one by one.
- b. Switch-ON the ROACH board by pressing the power ON/OFF switch.
- c. Switch-ON the Trigger Unit.
- d. Switch-ON the Hitite Signal Generator and set the frequency at 800MHz, Power at 7dbm and “EXT ON” using knob and button.

7. GPB System :

- a. Switch-ON all the machines in the rack one by one.
- b. Make sure all switches and fans in the racks are ON/working.